



Post-Closure Plan

J.H. CAMPBELL GENERATING FACILITY

DRY ASH LANDFILL POST-CLOSURE PLAN

West Olive, Michigan

Pursuant to 40 CFR 257.104

Submitted To: Consumers Energy Company

1945 W. Parnall Road Jackson, Michigan 49201

Submitted By: Golder Associates Inc.

15851 South US 27, Suite 50 Lansing, Michigan 48906

June 2018 1654923

A world of capabilities delivered locally






CERTIFICATION

Professional Engineer Certification Statement [40 CFR 257.104(d)(4)]

I hereby certify that, having reviewed the attached documentation and being familiar with the provisions of Title 40 of the Code of Federal Regulations Section 257.104 (40 CFR Part 257.104), I attest that this Post-Closure Plan is accurate and has been prepared in accordance with good engineering practices, including the consideration of applicable industry standards, and with the requirements of 40 CFR Part 257.104.

Golder Associates Inc.





Professional Engineer Certification Number





Table of Contents

CERTI	FICATION	C-1
Prof	essional Engineer Certification Statement [40 CFR 257.104(d)(4)]	C-1
1.0	INTRODUCTION	1
2.0	FACILITY CONTACT [40 CFR 257.104(d)(1)(ii)]	2
3.0	MONITORING AND MAINTENANCE ACTIVITIES [40 CFR 257.104(d)(1)(i, iii)]	3
3.1	Site Maintenance [40 CFR 257.104(d)(1)(i)]	3
3.2	Periodic Inspection Requirements [40 CFR 257.104(d)(1)(i)]	3
3.3	Site Use Restrictions [40 CFR 257.104(d)(1)(iii)]	∠
3.4	Groundwater Monitoring	∠
4.0	REFERENCES	6

i

List of Tables

Groundwater Detection Monitoring Constituents Groundwater Assessment Monitoring Constituents Table 3.4.1 Table 3.4.2

List of Figures

Figure 1 Site Location Map

Figure 2 Site Map

List of Appendices

Appendix A Appendix B

General Site Inspection Sheet Groundwater Sampling Analysis and Procedure Plan





1.0 INTRODUCTION

On April 17, 2015, the United States Environmental Protection Agency (EPA) issued the Coal Combustion Residual (CCR) Resource Conservation and Recovery Act (RCRA) Rule (40 CFR 257 Subpart D) ("CCR RCRA Rule") to regulate the beneficial use and disposal of CCR materials generated at coal-fired electrical power generating complexes. In accordance with the CCR RCRA Rule, any CCR surface impoundment or CCR landfill that was actively receiving CCRs on the effective date of the CCR RCRA Rule (October 19, 2015) was deemed to be an "Existing CCR Unit" on that date and subject to self-implementing compliance standards and schedules. Consumers Energy Company (CEC) currently operates the Dry Ash Landfill CCR unit (Dry Ash Landfill) at the J.H. Campbell Generating Facility (JH Campbell). JH Campbell is located in West Olive, Michigan as presented on Figure 1 – Site Location Map. The location of the Dry Ash Landfill is presented on Figure 2 – Site Map.

The intent of the post-closure plan is to assure that integrity and effectiveness of the final cover is maintained over the 30-year post-closure care period. The Dry Ash Landfill is anticipated to be certified closed by January 1, 2041 with the post-closure care period lasting through December 31, 2071.





2.0 FACILITY CONTACT [40 CFR 257.104(d)(1)(ii)]

The post-closure point of contact for the Dry Ash Landfill at JH Campbell is:

Michelle Marion 1945 W Parnall Road Jackson, Michigan 49201 (517) 788-5824 michelle.marion@cmsenergy.com





3.0 MONITORING AND MAINTENANCE ACTIVITIES [40 CFR 257.104(d)(1)(i, iii)]

3.1 Site Maintenance [40 CFR 257.104(d)(1)(i)]

The following general site maintenance and monitoring will be conducted to ensure the integrity and effectiveness of the final cover system:

- Fertilizer will be applied in areas of stressed or poor quality cover vegetation as needed.
- Vegetative cover will be mowed as needed to restrict uncontrolled woody plant establishment on the cover for the remainder of the 30-year post-closure period (estimated through 2063). This includes mowing the side slopes around the perimeter of the Dry Ash Landfill.
- Areas of erosion, including erosion from runoff or vehicle use, will be repaired by restoring the thickness of the protective cover and topsoil and seeding as necessary upon discovery.
- Erosion repairs will utilize clean soils. Typically, repair is expected to involve minor regrading, spreading of small amounts of additional soil, and reseeding. Areas of repeated erosion will be evaluated to determine if additional protection such as erosion blankets or riprap should be added.
- Groundwater monitoring system will be maintained in accordance with applicable requirements from 40 CFR 257.90 to 40 CFR 257.98.
- The leachate collection and removal system will be maintained in accordance with applicable requirements from 40 CFR 257.70(d).
- Differential settlement will be repaired as follows:
 - Minor differential settlement in which no ponding can occur or in which the subsurface drainage will not be compromised shall be repaired by stripping topsoil, adding sandy soil, and replacing topsoil to attain a smooth surface before seeding.
 - If differential settlement has occurred to the extent that drainage is compromised, surface soils shall be removed in the area to expose the geomembrane. The geomembrane shall be cut back and sand added to attain the line grade. Geomembrane, protective soil, and topsoil shall be replaced and seeded with repair certification maintained in the site files.

Areas requiring repair due to erosion or settlement will be identified during annual site inspections which are detailed below in Section 3.2.

3.2 Periodic Inspection Requirements [40 CFR 257.104(d)(1)(i)]

Periodic site inspections verifying the integrity and effectiveness of the final cover system will be conducted throughout the 30-year post-closure period (estimated through 2071) on no less than an annual basis. When and if items requiring construction and/or maintenance are identified during an inspection, CEC will schedule and conduct repairs promptly while noting the risk associated with the deficiency. During site inspections, the inspector will walk the entire closed Dry Ash Landfill area and document the problematic items on the "General Site Inspection Sheet" provided in Appendix A.



If maintenance is required, only low ground-pressure tire or track equipment should be utilized to correct the deficiencies on closed portions of the Dry Ash Landfill. Larger equipment can be used, but the equipment loading cannot exert more than five pounds per square inch (psi) on the liner material.

If repairs to the geosynthetics (e.g., geomembrane, geotextile, etc.) are necessary, a certified geosynthetic installer must conduct the repairs under the direction of a quality assurance representative. Repairs will be documented in a report, and a copy will be placed in the site's operating record.

3.3 Site Use Restrictions [40 CFR 257.104(d)(1)(iii)]

Currently, the identified end use for the Dry Ash Landfill at JH Campbell has been limited to securing the area and maintaining the site as described in Sections 3.1 and 3.2. If the area is to be developed in the future, the integrity of the geomembrane cover liner shall be confirmed with the proposed use; and institutional controls for maintaining the integrity of the geomembrane cover will be provided through an update to the post-closure plan. Once certified closed, CEC will ensure that the existing Restrictive Covenant recorded on February 12, 1999 conforms to the notation on the deed to the property required in 40 CFR 257.102(i).

Use of the site will be restricted by either fencing and gating or procedure to prohibit access other than for inspections, maintanence, and monitoring; established easements; and to restrict the use of intrusive vehicles and activities at the site.

3.4 Groundwater Monitoring

Twenty-one groundwater monitoring wells were installed around the Dry Ash Landfill to establish a groundwater monitoring system under 40 CFR 257.91(e)(1) during the fourth quarter of 2015. The groundwater monitoring well locations are provided on Figure 2 – General Site Plan. The groundwater monitoring wells were used to collect data for an initial annual groundwater monitoring and corrective action report per 40 CFR 257.90(e), which was posted in the operating record in January 2018. In conformance with 40 CFR 257.93, a groundwater sampling and analysis plan was developed for the groundwater monitoring program. The plan is included in Appendix B – Groundwater Sampling Analysis and Procedure Plan and includes direction on how to perform or acquire the following:

- Groundwater elevations
- Sample collection and handling procedures
- Equipment decontamination procedures
- Chain of custody control
- Sample preservation and shipment

- Quality assurance/Quality control (QA/QC)
- Investigation derived waste (IDW)
- Field documentation
- Analytical suite and procedures
- Optional additional analyses
- Data evaluation





Once the CCR unit is certified closed, post-closure periodic groundwater samples will be collected at least semi-annually and analyzed for 30 years for the following constituents in Table 3.4.1 – Groundwater Detection Monitoring Constituents.

Table 3.4.1 – Groundwater Detection Monitoring Constituents

Common Name			
Boron Fluoride			
Calcium	Sulfate		
Chloride	Total Dissolved Solids (TDS)		
рН	-		

If a statistically significant increase over background levels for one or more of the constituents listed in Table 3.4.1 is detected during groundwater detection monitoring, then CEC will follow the procedures outlined in 40 CFR 257.93(h) and 257.94(e). If required by 40 CFR 257.94(e), an assessment groundwater monitoring program will be established meeting the requirements of 40 CFR 257.95 for the constituents presented in Table 3.4.2 – Groundwater Assessment Monitoring Constituents. The data will presented in an annual groundwater monitoring and corrective action report per 40 CFR 257.90(e).

Table 3.4.2 – Groundwater Assessment Monitoring Constituents

Common Name					
Antimony	Mercury				
Arsenic	Cobalt	Molybdenum			
Barium	Fluoride	Selenium			
Beryllium	Lead	Thallium			
Cadmium	Lithium	Radium 226 and 228 combined			

The annual groundwater monitoring and corrective action reports will be:

- Maintained in the JH Campbell operating record per 40 CFR 257.105(h)(1)
- Submitted to the Michigan Department of Environmental Quality (MDEQ) per the notification requirement in 40 CFR 257.106(h)(1)
- Posted on a publicly accessible internet website per 40 CFR 257.107(h)(1)

If additional notification is warranted, CEC will notify appropriate parties per 40 CFR 257.106(h).





4.0 REFERENCES

"Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments," Title 40 – Protection of the Environment Part 257 – Criteria for Classification of Solid Waste Disposal Facilities and Practices Subpart D – Standards for the Disposal of Coal Combustion Residuals in Landfills and Surface Impoundments.



Established in 1960, Golder Associates is a global, employee-owned organization that helps clients find sustainable solutions to the challenges of finite resources, energy and water supply and management, waste management, urbanization, and climate change. We provide a wide range of independent consulting, design, and construction services in our specialist areas of earth, environment, and energy. By building strong relationships and meeting the needs of clients, our people have created one of the most trusted professional services organizations in the world.


Africa + 27 11 254 4800 Asia + 852 2562 3658 Australasia + 61 3 8862 3500 Europe + 356 21 42 30 20 North America + 1 800 275 3281 South America + 56 2 2616 2000

solutions@golder.com www.golder.com

Golder Associates Inc. 15851 South U.S. 27, Suite 50 Lansing, MI 48906 USA Tel: (517) 482-2262

Fax: (517) 482-2460









REFERENCE(S)

 BASE MAP TAKEN FROM 7.5 MINUTE U.S.G.S. QUADRANGLES OF PORT SHELDON MICHIGAN, DOWNLOADED FROM MICHIGAN DNR WEBSITE JUNE 2016.



CLIENT

CONSUMERS ENERGY COMPANY 17000 CROSWELL ST. WEST OLIVE, MI 49460

CONSULTANT



YYYY-MM-DD	2016-06-06
DESIGNED	BAL
PREPARED	ARM
REVIEWED	DJS
APPROVED	MAB


PROJECT

J.H. CAMPBELL GENERATING FACILITY DRY ASH LANDFILL POST-CLOSURE PLAN

TITLE

SITE LOCATION MAP

PROJECT NO.	REV.	FIGURE
1654923	#	1



APPENDIX A
GENERAL SITE INSPECTION SHEET



GENERAL SITE INSPECTION J.H. CAMPBELL DRY ASH LANDFILL CLOSURE AREA

Inspector:		Inspection Date:			
Post Closure Manager:		Review Date:			
SITE CONDITIONS	ı				
Weather:	Temper	rature:			
Precipitation:	Wind:				
		_			
INSPECTION TASKS 1) Note areas of erosion (gullies exceeding 6 inches deeple and the second	nn)				
1) Note areas of erosion (guilles exceeding 6 inches dee	εp).				
2) Note areas of sedimentation.					
3) Note areas of settlement that have compromised surf	ace drain	age controls.			
4) Note areas of ponding.					
5) Note areas of vegetative stress.					
6) Note areas of woody plant growth.					
7) Note location of animal burrows.					
8) Condition of ditches, culverts, and channels.					
,					





GENERAL SITE INSPECTION J.H. CAMPBELL DRY ASH LANDFILL CLOSURE AREA

9) Condition of site access road(s), silt fences surrounding the site.
10) Condition of fencing and gates.
11) Proper site restriction signage.
12) Miscellaneous findings.
ADDITIONAL COMMENTO
ADDITIONAL COMMENTS
CORRECTIVE ACTION PLAN (To Be Completed by Post Closure Manager)



APPENDIX B
GROUNDWATER SAMPLING ANALYSIS AND PROCEDURE PLAN



Consumers Energy Company

ELECTRIC GENERATION FACILITIES RCRA CCR DETECTION MONITORING PROGRAM

JH Campbell Monitoring Program Sample and Analysis Plan West Olive, Michigan

May 18, 2016

Nuklaus R.H. Well

Nicklaus Welty, PG Senior Geologist

Mark Klemmer, PE

Technical Expert/Associate Vice President

lad Klemmer

Gregory E. Zellmer, PG

Certified Project Manager/Senior Geologist

ELECTRIC GENERATION FACILITIES RCRA CCR DETECTION MONITORING PROGRAM

JH Campbell Monitoring Program Sample and Analysis Plan

Prepared for:

Consumers Energy Company

Jackson, Michigan

Prepared by:

Arcadis of Michigan, LLC

10559 Citation Drive

Suite 100

Brighton

Michigan 48116

Tel 810 229 8594

Fax 810 229 8837

Our Ref.:

DE000722.0002.00004

Date:

May 18, 2016

This document is intended only for the use of the individual or entity for which it was prepared and may contain information that is privileged, confidential and exempt from disclosure under applicable law. Any dissemination, distribution or copying of this document is strictly prohibited.

CONTENTS

1	Introd	luction	1
2	Purpo	ose and Objectives	1
3	Imple	mentation and Sampling Schedule	1
4	Samp	ole Collection and Handling Procedures	2
	4.1	Groundwater Elevations	2
	4.2	Groundwater Sample Collection	3
	4.3	Sample Preservation and Shipment	4
	4.4	Quality Assurance/Quality Control (QA/QC)	4
	4.5	Equipment Decontamination Procedures	5
	4.6	Investigation Derived Waste (IDW)	5
	4.7	Field Documentation	5
5	Analy	rtical Suite and Procedures	6
	5.1	Optional Additional Analyses	7
6	Data	Evaluation	8

TABLES

Table 1 Monitoring Well Construction Details

FIGURES

Drawing SG-22345 - Campbell Plant Monitoring Wells, CCR Monitoring

APPENDICES

- A Low Stress (Low Flow) Purging and Sampling of Groundwater Monitoring Wells SOP (Procedure CHEM-2.7.06)
- B Chain-of-Custody, Handling, Packing and Shipping SOP (Procedure CHEM-1.2.04)

1 INTRODUCTION

ARCADIS has prepared this Groundwater Sampling and Analysis Plan (SAP) to evaluate background and downgradient groundwater quality at the JH Campbell electric generation facility (JHC), located in West Olive, Michigan (Site). The collection of groundwater data will be completed to achieve compliance under the recently published 40 CFR Part 257, Subpart D – Standards for the Disposal of Coal Combustion Residuals (CCR) in Landfills and Surface Impoundments. The methodologies outlined in this SAP are consistent with the regulations, general federal and state guidance, ARCADIS and Consumers Energy (CE) Standard Operating Procedures (SOPs), and industry standards.

2 PURPOSE AND OBJECTIVES

The groundwater monitoring and corrective action compliance requirements for existing CCR units are set forth in 40 CFR 257.90 through 257.98. The groundwater sampling and analysis requirements detailed in 40 CFR 257.93, and require the development of a SAP which details the sampling and analysis procedures that will be utilized to provide an accurate representation of groundwater quality at the background and downgradient wells. As per, 40 CFR 257.93 a) this SAP includes a description of the procedures and techniques that will be implemented for:

- Sample collection
- · Sample preservation and shipment
- Analytical procedures
- Chain of custody control
- Quality assurance and quality control

3 IMPLEMENTATION AND SAMPLING SCHEDULE

As set forth in 40 CFR 257.93, eight (8) background detection monitoring events must be completed by October 17, 2017. Establishment of a groundwater monitoring system is necessary for the JH Campbell Cells 1-4 (CCR Landfill) and Bottom Ash Ponds 1-2, N/S, Bottom Ash Ponds 1-2, N/S, and Pond A (CCR Surface Impoundments). Background and detection monitoring events will be completed concurrently by comparison of data from monitoring wells located both away from (background) and downgradient of any impoundments still receiving ash as of the implementation date of the rule (October 19, 2015).

The sampling events will be distributed to account for seasonal variability and will be spaced at least 30 days apart to be considered statistically independent. The following is a general schedule to be followed assuming a quarterly sampling interval beginning December 2015 and ending September 2017. Minor modification to the timing of sampling events can be made as long as the requirements listed above are still met. This schedule may be shifted to start in the fourth quarter of 2015 pending timing of well installation and development.

Event 1 – 4th Quarter 2015 (December)

- Event 2 1st Quarter 2016 (March)
- Event 3 2nd Quarter 2016 (June)
- Event 4 3rd Quarter 2016 (September)
- Event 5 4th Quarter 2016 (December)
- Event 6 1st Quarter 2017 (March)
- Event 7 2nd Quarter 2017 (June)
- Event 8 3rd Quarter 2017 (September)

Resampling of a well due to an anomalous result, either relative to data collected from other monitoring wells of similar type, or relative to other time-series data at an individual monitoring well may be completed at any time. The timing of the resampling event, and the reason for additional data collection will determine if events are statistically dependent and inform the appropriate method for addressing interpretation or inclusion of data. Additional analytes may also be required pending the results of the quarterly monitoring events (in accordance with Section 257.94(e)). This document does not cover collection and analysis of such additional data.

4 SAMPLE COLLECTION AND HANDLING PROCEDURES

The following sections address the methods and procedures associated with the collection and handling of groundwater samples at the Site. The monitoring well locations are shown in Drawing SG-22345, and relevant construction details and monitoring purpose (e.g. background or downgradient) provided in Table 1. A total of thirty-seven (37) monitoring wells were installed at the JH Campbell facility to assess groundwater quality within the uppermost aquifer, which consists of a shallow aquifer approximately 5-35 feet below ground surface. Eight (8) monitoring wells are designated as background monitoring wells with the remaining wells to monitor downgradient groundwater quality for comparison (Drawing SG-22345). Of the 37 monitoring wells, three (3) wells are existing monitoring wells, designated as follows:

Historical Well Name	RCRA Well Name
MW-B4	JRW MW-15035
MW-B6	JRW MW-15036
MW-B7	JRW MW-15037

4.1 Groundwater Elevations

Groundwater level data will be collected from all monitoring wells during each sampling event, prior to sampling. The monitoring well locations are depicted on Drawing SG-22345. Groundwater level monitoring will be conducted in accordance with Section 9.2 of the Low Stress (Low Flow) Purging and Sampling of Groundwater Monitoring Wells SOP presented in Appendix A.

Upon arrival at the site, all monitoring wells will be opened and allowed to equilibrate with ambient air pressures prior to measuring the depths to water. Groundwater level measurements will then be made to the nearest 0.01 foot with an electronic water level indicator from the entire monitoring well network prior to sampling – monitoring wells that constitute a groundwater monitoring system for a CCR Unit shall be preferentially sampled in order to further minimize water level elevational changes relative to the CCR Unit.. The entire monitoring well network shall be gauged on the same day to minimize temporal bias of measured groundwater elevation changes for the monitoring well network.

Depth to water will be measured from established top of casing reference points. Groundwater levels, well conditions, and any pertinent observations will be recorded on the depth to water level measurements field log provided in Appendix A.

The measured hydraulic gradient will be used along with previously completed hydraulic conductivity testing to estimate the apparent groundwater gradient during each sampling event.

4.2 Groundwater Sample Collection

Groundwater samples will be collected from the monitoring wells following Low-Flow (Minimal Drawdown) Groundwater Sampling Procedures (US EPA, 1996), as detailed in the Low Stress (Low Flow) Purging and Sampling of Groundwater Monitoring Wells SOP (Appendix A). Low flow sampling will commence with the installation of either a peristaltic, stainless-steel 12-volt submersible impeller pump or bladder pump to a depth representing the middle of the saturated screen interval. An appropriate length of polyethylene tubing will be connected to the pump discharge prior to pump placement. The discharge line will be connected to a flow-cell and multi-meter to collect water quality indicator parameters (described below) during well purging to determine water quality stabilization.

The pump will be operated at a flow rate that will ensure low volatilization and low well disturbance. Water quality indicator parameters and depth to water will be recorded at 3 to 5 minute intervals during the purging process and recorded on the sampling worksheet provided in Appendix B. Purging and sampling will proceed at a low pumping rate, expected to be 0.5 liters per minute or less, such that the water column in the well is not lowered more than 0.3 feet below the initial static depth to water measurement. The subject well will be considered ready to sample when three consecutive water quality measurements meet the stabilization criteria presented below.

Parameter	Stabilization Criteria
рН	3 readings within +/- 0.1 standard units (SU)
Specific Conductance	3 readings within +/- 3% millisiemens per centimeter (mS/cm)
Temperature	For Information Only
Turbidity	+/- 10% Nephelometric Turbidity Unit (NTU) variance between three consecutive readings and a turbidity less than 10 NTU
Oxygen Reduction Potential (ORP)	3 readings within +/- 10 millivolts (mV)
Dissolved Oxygen (DO)	3 readings within +/- 0.3 milligrams per liter (mg/L)

If the well is dry, no attempt at sampling will be conducted, as the aquifer is not considered to have sufficient quantity at that location. Additionally, if the well is pumped dry during low-flow monitoring activity, the well will be left overnight to accumulate water, then a sample collected assuming the NTU criteria can be met. Prior to use, all equipment will be calibrated in accordance with the manufactures recommendations. Calibration information will be recorded in the field book.

4.3 Sample Preservation and Shipment

Samples will be collected immediately following stabilization of field parameters as set forth in in the preceding section. Groundwater samples will be collected into the laboratory provided sample containers required for the analyses specified in the following section. The groundwater samples will be collected from the discharge tubing upstream of the water quality meter flow cell. Care will be taken to allow for a non-turbulent filling of laboratory containers. Routine samples will not be filtered in the field to provide a measure of total recoverable metals that will include both the dissolved and particulate fractions of metals as per the rule.

If a more detailed understanding of the source of metals concentrations in groundwater is required for select monitoring wells, field filtered samples may be analyzed in addition to routine analysis. Field filtering may also be completed on highly turbid samples (greater than 10 NTU). Field filtering will be completed using a 0.45 micron filter. If required, an attempt will be made to redevelop any monitoring wells that produce highly turbid samples prior to the subsequent sampling event. Where samples are filtered, a corresponding, unfiltered sample will also be collected.

The samples will be labelled, stored and transported to the laboratory according to the Chain-of-Custody, Handling, Packing and Shipping SOP presented in Appendix C. Following collection, samples will be immediately labelled, logged on the chain-of-custody, and placed in a cooler with ice. Sample coolers transported to the laboratory via overnight or next day air freight will be sealed with packing tape and a signed Chain-of-Custody seal. Sample coolers transported to the laboratory directly must be secured to ensure sample integrity is maintained. The samples will be packaged and shipped according to U. S. Department of Transportation and EPA regulations. The documentation of actual sample storage and transport will be by the use of chain-of-custody procedures. A laboratory provided chain-of-custody record will contain the dates and times of collection, receipt, and completion of all the analyses on a particular set of samples. The laboratory will return a copy of the chain-of-custody with the analytical report.

4.4 Quality Assurance/Quality Control (QA/QC)

Quality assurance/quality control (QA/QC) samples will be collected to ensure sample containers are free of analytes of interest, assess the variability of the sampling and laboratory methods, and monitor the effectiveness of decontamination protocols. The following QA/QC samples will be collected during each groundwater sampling event:

Field duplicates will be collected at a frequency of one duplicate sample per 10 groundwater samples
with at least one duplicate collected from each Unit. The field duplicates will be collected at the same
time and in the same manner as the original sample. The duplicates will be labeled as a blind sample
and noted on the sampling form of the designated well.

- Matrix spike/matrix spike duplicate (MS/MSD) samples will be collected at a frequency of one MS/MSD sample per 20 groundwater samples with at least one MS/MSD from each Unit. Duplicate and MS/MSD samples will be collected from different monitoring wells.
- Field blanks will be collected at a frequency of one field blank per 20 groundwater samples with at least one field blank collected from each Unit.
- Equipment blanks will be collected at a frequency of one equipment blank per 10 groundwater samples with at least one equipment blank collected from each Unit. The equipment blank will be collected by pouring distilled or deionized water over the decontaminated static water level meter or low flow pump and into the laboratory supplied containers.

Based on the number of Units at the Campbell facility (five Units) and wells per Unit, a total of 5 field duplicates, 5 MS/MSD, 5 field blanks, and 5 equipment blanks will be collected during each sample event. The QA/QC samples will be submitted to the laboratory for the routine analyses specified in Section 5 and in Appendix III and IV to Part 257. The laboratory should provide adequate documentation of laboratory reporting and QA/QC procedures.

4.5 Equipment Decontamination Procedures

All non-dedicated equipment will be decontaminated prior to use and between samples, following procedures presented in paragraph 9.6 of the SOP in Appendix A. Non-dedicated equipment will include a water level meter and low flow sampling pump (submersible). Each item will be cleaned using distilled or deionized water, and when necessary, non-phosphate detergent wash followed by a distilled or deionized water rinse. When a peristaltic pump is used for low flow sampling, decontamination is not required, only replacement of the pump head tubing.

All dedicated equipment will be disposed of after each sampling point. Dedicated equipment will include polyethylene tubing and bladders if a bladder pump is used for low-flow sampling.

The flow-cell and water quality multi-meter (sonde) will be decontaminated at the completion of low-flow sampling. All sample collection will occur upstream of this device and therefore will not affect groundwater sample analytical results.

4.6 Investigation Derived Waste (IDW)

All waste created during monitoring well sampling will remain on site. All purge water from wells installed within the CCR Units will be discharged back onto the ground near the well it was purged from. All purge water from wells installed outside of a CCR Unit will be discharged to the ground in a manner that it doesn't directly enter a surface water or drain. All IDW will be handled according to details provided in paragraphs 9.3.8 and 9.4.10 of the SOP provided in Appendix A.

4.7 Field Documentation

All information pertinent to the field activities and sampling efforts will be recorded in a log or notebook, following the documentation procedures presented in section 5.4 of the SOP in Appendix B. Field logs

are provided in the Attachments to Appendix A. At a minimum, entries in the sample logs will include the following:

- Property details and location
- Type of sample (for example, groundwater, surface water, waste)
- Number and volume of samples taken
- Sampling methodology
- · Date and time of collection
- Sample identification number(s)
- Field observations including weather
- Any field measurements made (for example, pH, temperature, water depth and air monitoring data)
- Personnel present

Records shall contain sufficient information so that the sampling activity can be reconstructed without relying on the collector's memory. The sample logs will be preserved in electronic format.

5 ANALYTICAL SUITE AND PROCEDURES

As required for existing CCR units, all groundwater samples collected at the JHC facility will be submitted to the laboratory for the analyses specified in Appendix III and IV to Part 257. The analytical methods and reporting limits for each constituent are summarized below. If required, and in consultation with the laboratory, a comparable analytical method may be substituted for the analytical method recommended below. All groundwater samples will be submitted to Consumers Energy Trail Street Laboratory. If any analyses are subsequently subcontracted to another accredited laboratory, the samples will be shipped using appropriate methods and COC documentation. All analyses will be performed within required hold times and consistent with the data quality objectives of this SAP.

Appendix III to Part 257—Constituents

Constituent	Analytical method	Preservation	Hold Time (Days)	Reporting Limit (μg/L)
Boron	EPA 6020B	HNO ₃ , pH <2	180	20
Calcium	EPA 6020B	HNO ₃ , pH <2	180	1,000
Chloride	EPA 300.0	None, <6°C	28	1,000
Fluoride#	EPA 300.0	None	28	1,000
рН	Stabilized field measurement	NA	NA	0.1 standard units
Sulfate	EPA 300.0	None, <6°C	28	2,000
Total Dissolved Solids	SM 2540C	None, <6°C	7	1,000

HNO₃ - Nitric acid

NA – Not applicable

Appendix IV to Part 257—Constituents

Constituent	Analytical method	Preservation	Hold Time (Days)	Reporting Limit (μg/L)
Antimony	EPA 6020B	HNO₃, pH <2	180	1
Arsenic	EPA 6020B	HNO ₃ , pH <2	180	1
Barium	EPA 6020B	HNO₃, pH <2	180	5
Beryllium	EPA 6020B	HNO₃, pH <2	180	1
Cadmium	EPA 6020B	HNO₃, pH <2	180	0.2
Chromium, total	EPA 6020B	HNO₃, pH <2	180	1
Cobalt	EPA 6020B	HNO ₃ , pH <2	180	15
Fluoride#	EPA 300	None, <6°C	28	1,000
Lead	EPA 6020B	HNO ₃ , pH <2	180	1
Lithium	EPA 6020B	HNO₃, pH <2	180	10
Mercury	EPA 7470A	HNO ₃ , pH <2	28	0.2
Molybdenum	EPA 6020B	HNO₃, pH <2	180	5
Selenium	EPA 6020B	HNO₃, pH <2	180	1
Thallium	EPA 6020B	HNO ₃ , pH <2	180	2
Radium 226 and 228 combined [^]	EPA 903.1/904.0	HNO₃, pH <2	None	1 picocurie per liter

[#] Listed in both Appendix III and Appendix IV

5.1 Optional Additional Analyses

To interpret groundwater monitoring data and determine the appropriate statistical methods for use in comparison of background and downgradient data sets, an understanding of aquifer connectivity and water types may be required. To determine if samples are collected from comparable aquifer units the predominant water type will be determined using Piper and Stiff diagrams.

Piper and Stiff diagrams are a graphical representation of the major anion and cation composition of a water sample and are useful in establishing if groundwater samples are from the same or a similar aquifer unit. To generate Piper and Stiff diagrams additional analytical data beyond that collected during routine sampling will be required. The additional analytical requirements are shown in the table below.

[^]Requires a larger sample volume (minimum 2 liter)

Constituent	Analytical method	Preservation	Hold Time (Days)	Reporting Limit (µg/L)
Bicarbonate, carbonate and total alkalinity	ASM 2320B	None, 6°C	14	10,000
Magnesium	EPA 6020B	HNO₃, pH <2	180	1,000
Sodium	EPA 6020B	HNO ₃ , pH <2	180	1,000
Potassium	EPA 6020B	HNO ₃ , pH <2	180	500

6 DATA EVALUATION

In accordance with 40 CFR 257.93 data collected from eight samples from each background well will be used to calculate background concentrations for each constituent at each site. Background concentrations for each constituent will be calculated using an appropriate statistical method for each background well and constituent pair at the site, selected based on the distribution of the data in accordance with 40 CFR 257.93.

The data collected from background and downgradient monitoring wells will be compared using an appropriate statistical method, to be determined based on the distribution of data for each constituent, to assess if downgradient concentrations are consistent with background concentrations for each constituent. The statistical method used for this analysis will be one, or a combination, of the four statistical methods described below and in 40 CFR 257.93(f) and will meet the performance standards outlined in 40 CFR 257.93(g).

A combination of statistical methods may be applied depending on the statistical distribution observed for each specified constituent in each monitoring well. The four specific statistical procedures provided in 40 CFR 257.93(f) are: (1) a parametric analysis of variance followed by multiple comparison procedures to identify statistically significant evidence of contamination; (2) an analysis of variance based on ranks followed by multiple comparison procedures to identify statistically significant evidence of contamination; (3) a tolerance or prediction interval procedure; and (4) a control chart approach.

The potential for seasonal and spatial variability as well as temporal trends will be considered when selecting the statistical method for comparison. Data will also be displayed graphically using box-and—whisker plots to aid in interpretation of the statistical analysis.

In order to select the appropriate method for statistical analysis for each constituent at each monitoring well, the distribution type for each constituent/well pair will be calculated. Normally distributed data will use parametric methods for comparisons and non-normally distributed data will use non-parametric methods, consistent with the requirements outlined in 40 CFR 257.93(g).

Statistical comparisons will be performed using a confidence level of 99 percent (alpha of 0.01) for comparisons of individual data point to background concentrations, and a confidence level of 95 percent (alpha of 0.05) where multiple data points will be compared to background, consistent with 40 CFR 257.93(g)

TABLES

Table 1 Monitoring Well Construction Summary Consumers Energy Co.
J.H. Campbell Generating Facility
West Olive, Michigan



1/1


	Former MW ID	Site Coordinates						Well	Caraan	Statio DTM		
MW ID		Northing	Easting	тос	Ground Elevation	Date Installed	Geologic Unit of Screen Interval	Well Construction	Screen Length (ft)	Screen Interval (ft bgs)	Static DTW (ft below TOC)	Total Depth
Pond A Downgradien	t MW											
JHC MW-15006		517535.73	12635481.66	624.74	627.58	9/18/2015	Silty Sand / Sand	2" PVC, 10 slot	10	25 - 35	28.90	38.02
JHC MW-15007		517540.50	12635742.72	624.82	627.70	9/21/2015	Sand	2" PVC, 10 slot	10	22 - 32	29.28	34.75
JHC MW-15008		517560.39	12636031.25	632.43	635.30	9/21/2015	Sand	2" PVC, 10 slot	10	28 - 38	38.25	40.76
JHC MW-15009		517779.13	12636014.80	632.33	635.32	9/22/2015	Sand	2" PVC, 10 slot	10	30 - 40	37.14	42.88
	_											
JHC MW-15010		518009.36	12636011.46	632.55	635.57	9/23/2015	Sand	2" PVC, 10 slot	10	30 - 40	36.57	42.88
JHC MW-15011		517540.50	12634931.59	627.71	630.83	9/23/2015	Sand	2" PVC, 10 slot	10	27 - 37	34.45	40.12
CCR Landfill (Cells I,2	2.3. and 4) Downgrad	dient MW										
JHC MW-15017	.,o, a.i.a ., 2011g.a.	521074.31	12635685.32	613.69	616.61	9/29/2015	Sand	2" PVC, 10 slot	10	10 - 20	15.56	22.98
JHC MW-15017		521074.51	12635979.61	614.26	617.02	9/28/2015	Sand	2" PVC, 10 slot	10	10 - 20	16.23	22.95
JHC MW-15019		521075.54	12636352.00	609.81	612.86	9/29/2015	Sand	2" PVC, 10 slot	10	6 - 16	12.78	19.11
JHC MW-15020		521059.97	12636589.95	609.04	611.90	9/30/2015	Sand	2" PVC, 10 slot	10	6 - 16	12.25	18.97
JHC MW-15021		521065.93	12636839.06	610.70	613.65	9/30/2015	Sand	2" PVC, 10 slot	10	6 - 16	14.38	18.30
JHC MW-15022		520479.72	12638430.24	620.92	623.79	9/30/2015	Sand	2" PVC, 10 slot	10	23 - 33	29.37	36.30
JHC MW-15031 JHC MW-15032		520118.00 520779.28	12637801.51 12638667.93	632.94 611.32	635.87 614.29	10/5/2015 10/6/2015	Sand Sand	2" PVC, 10 slot 2" PVC, 10 slot	10 10	33 - 43 13 - 23	43.19 17.81	46.17 26.04
JHC MW-15032		521075.81	12638598.12	618.08	620.99	10/6/2015	Sand	2" PVC, 10 slot	10	16 - 26	22.93	28.78
JHC MW-15033		521335.83	12638568.90	612.90	615.97	10/6/2015	Sand	2" PVC, 10 slot	10	11 - 21	16.81	23.98
JHC MW-15034 JHC MW-15035	MW-B5	520112.93	12637510.26	632.53	634.28	3/14/2001	Sand	2" PVC, 10 slot	10	33 - 43	NA	23.96 NA
JHC MW-15035	MW-B6	520099.80	12638094.34	617.94	618.34	3/13/2001	Sand	2" PVC, 10 slot	10	20 - 30	NA NA	NA NA
JHC MW-15037	MW-B7	520083.04	12638436.69	614.28	616.06	8/29/2001	Sand	2" PVC, 10 slot	10	23 - 28	NA	NA
		P 4 88184				-	•			•		
Bottom Ash Pond Uni	t 1-2N/1-2S Downgr		40000400.04	007.00	000.50	9/16/2015	01	01 DVO 40 -1-4	-	0.5.05	0.04	44.70
JHC MW-15001		518586.88 518378.92	12633422.01 12633974.82	607.02 625.97	609.53 628.87	9/16/2015	Sand Sand	2" PVC, 10 slot 2" PVC, 10 slot	5 10	3.5 - 8.5 28 - 38	9.31 24.51	11.72 41.05
JHC MW-15002 JHC MW-15003		518378.92		628.31	630.63	9/16/2015	Sand	2" PVC, 10 slot	10	28 - 38	30.57	40.12
JHC MW-15003 JHC MW-15004		517864.56	12633990.37 12633547.12	624.92	628.44	9/17/2015	Sand	2" PVC, 10 slot	10	24 - 34	31.67	37.48
JHC MW-15004		517781.42	12633905.01	624.37	627.30	9/18/2015	Sand	2" PVC, 10 slot	10	27 - 37	33.26	40.10
JITIC WW-13003		317761.42	12033903.01	024.37	027.30	9/16/2013	Sanu	2 FVC, 10 Slot	10	21 - 31	33.20	40.10
Bottom Ash Pond Uni	t 3N/3S Downgradie						_					
JHC MW-15012		519214.84	12633675.28	632.59	635.66	9/28/2015	Sand	2" PVC, 10 slot	10	28 - 38	28.70	40.96
JHC MW-15013		519207.19	12634025.15	632.40	635.25	9/25/2015	Sand	2" PVC, 10 slot	10	28 - 38	25.94	41.15
JHC MW-15014		519419.85	12634254.12	635.13	638.18	9/25/2015	Sand	2" PVC, 10 slot	10	39 - 49	29.81	52.00
JHC MW-15015		519715.11	12634186.63	632.46	635.20	9/28/2015	Sand	2" PVC, 10 slot	10	28 - 38	28.57	41.28
JHC MW-15016		519956.79	12634198.52	631.81	634.64	9/28/2015	Sand	2" PVC, 10 slot	10	28 - 38	30.33	41.06
Background MW					1	L	I	L	1	1		
JHC MW-15023		521927.21	12638205.16	617.01	619.98	10/1/2015	Sand	2" PVC, 10 slot	10	14 - 24	18.91	27.68
JHC MW-15024		522366.01	12637322.68	613.79	616.62	10/1/2015	Sand	2" PVC, 10 slot	10	7 - 17	14.12	19.93
JHC MW-15025		522702.98	12636668.15	614.14	617.17	10/1/2015	Sand	2" PVC, 10 slot	10	7 - 17	13.50	19.94
JHC MW-15026		522495.09	12635971.82	615.09	618.04	10/2/2015	Sand	2" PVC, 10 slot	10	8 - 18	15.34	21.02
JHC MW-15027		522394.86	12635097.51	614.77	617.30	10/2/2015	Sand	2" PVC, 10 slot	10	10 - 20	15.85	22.99
JHC MW-15028		521646.20	12634105.34	611.02	613.80	10/2/2015	Sand	2" PVC, 10 slot	10	8 - 18	14.38	20.82
JHC MW-15029		520503.52	12633774.30	608.08	610.95	10/5/2015	Sand	2" PVC, 10 slot	10	8 - 18	10.03	20.96
JHC MW-15030		519760.83	12633044.37	604.05	607.17	10/5/2015	Sand	2" PVC, 10 slot	10	4 - 14	7.99	16.93

Notes:

tt = feet
bgs = below ground surface
TOC = top of casing
NR = Not recorded

NA = Not applicable

FIGURES



SURVEY REPORT

Horizontal: State Plane Coordinates were obtained on the monitor wells using RTK GPS using the CORS network. The horizontal datum is Michigan State Plane Coordinates, Michigan South Zone, NAD83 (2011 Adjustment, Epoch

Vertical: Elevations are on NAVD 88 datum. All elevations were established on the monitor wells using closed and adjusted level loops from known JHC plant

SURVEYOR'S NOTES

1) Utility locations are derived from actual measurements or available records. They should not be interpreted to be exact locations nor should it be assumed that they are the only utilities in this area.

2) NOTE TO CONTRACTORS: 3 (THREE) WORKING DAYS BEFORE YOU DIG, CALL MISS DIG AT TOLL FREE 1-800-482-7171 FOR UTILITY

LOCATIONS ON THE GROUND. 3) 2012 aerial imagery provided by Consuemers Energy.

LEGEND

= EXISTING MONITORING WELL

= DOWNGRADIENT LANDFILL MONITORING WELL

= DOWNGRADIENT BOTTOM ASH POND 1/2 N/S MONITORING WELL


= DOWNGRADIENT BOTTOM ASH POND 3 N/S MONITORING WELL


= POND A MONITORING WELL

= BACKGROUND MONITORING WELL

BASIS OF BEARING STATE PLANE COORDINATES

BASIS OF ELEVATION NEDI BM (NAVD88)





AVAILABLE RECORDS. THEY SHOULD NOT BE INTERPRETED TO BE EXACT LOCATIONS NOR SHOULD IT BE ASSUMED THAT THEY ARE THE ONLY UTILITIES IN THIS AREA. NOTE:
EXISTING UTILITIES AND SERVICE LINES IDENTIFIED AS "(PLAN)" WERE OBTAINED FROM AVAILABLE CITY AS-BUILT RECORD DRAWINGS. THE CONTRACTOR SHALL VERIFY THE LOCATION, DEPTH AND STATUS OF ALL UTILITIES AND SERVICE LINES PRIOR TO NEW CONNECTIONS.

BENCHMARKS

BENCHMARK #150 ELEV. = 611.72 (NAVD88) Set railroad spike in West side of power pole 32'± East of centerline of old Hiawatha Drive, 1000'± North of Polk

BENCHMARK #151 ELEV. = 612.77 (NAVD88)

Set on top of top bolt on West side of Northwest tower leg of middle tower of three running North-South.

BENCHMARK #152 ELEV. = 620.75 (NAVD88)

Set on top of top bolt on Southwest side of South tower leg of North-most tower.

BENCHMARK #153 ELEV. = 618.84 (NAVD88) Set on top of top bolt on North side of Northwest tower leg.

BENCHMARK #154 ELEV. = 614.44 (NAVD88) Set on top of top bolt on North side of Northwest tower leg, 50'± East of two-track to North extended.

BENCHMARK #155 ELEV. = 619.32 (NAVD88) JHC Control Point #33 monument, 100'± South and 100'± West of woods line in Northeast corner of site.

BENCHMARK #156 ELEV. = 617.12 (NAVD88) JHC Control Point #34 monument, approximately at top of bank, Southeast part of site, 60'± Southeast of gravel

drive, approximately at Southeast corner of grassy mound. BENCHMARK #157 ELEV. = 630.91 (NAVD88)

JHC Control Point #35 monument, 7'± South of South edge of gravel drive, 120'± West of centerline of gravel to South, approximately at Southwest corner of grassy mound. BENCHMARK #158 ELEV. = 631.45 (NAVD88)

JHC Control Point monument, no #, on top of bank approximately at point of intersection of gravel road to North and Southwest, 22'± South of centerline of gravel road at Southeast corner of site.

JHC Control Point monument, no #, 0.5' above ground level, approximately at point of intersection of centerline of gravel road to Northeast and West 30'± South of centerline of gravel road on top of bank.

BENCHMARK #160 ELEV. = 631.70 (NAVD88) JHC Control Point monument, 0.25'± above ground level, at top of bank 22'± South of centerline "T" intersection of gravel drive roads going East, West and North, approximately at centerline point of intersection of centerline to North and East.

BENCHMARK #161 ELEV. = 628.67 (NAVD88)

BENCHMARK #159 ELEV. = 632.77 (NAVD88)

Set railroad spike in Northwest side of light pole, 5' West of fence, 100'± South of Northwest corner of fence surrounding a pond and a metal building, approximate Southwest part of site.

BENCHMARK #162 ELEV. = 633.81 (NAVD88)

Set on top of bolt on East side on East side of Southeast tower leg, North-most tower of three, North and East of Monitor Well 15013 (Tower #6810).

BENCHMARK #163 ELEV. = 635.03 (NAVD88)

Set on top of steel post holding bird house #150, across gravel road from Northeast corner of ash pond.



JHC MW-15012

JHC MW-15014





JHC MW-15018





Randal J. Vugteveen Professional Surveyor No. 28429 Nederveld, Inc. rvugteveen@nederveld.com

SURVEY POINT	INSTRUMENTATION			GROUND ELEVATION	TOP OF CASING		
NUMBER	STRUCTURE	NORTHING	EASTING	(TOP OF CONCRETE)	ELEVATION	LATITUDE	LONGITUDE
NOIVIBLIX	STRUCTURE	NAD83 ADJ.2011 IN	İTERNATIONAL FT.	(NAVD88)	(NAVD88)	(DECIMAL	DEGREES)
70035	JHC MW-15001	518586.883	12633422.010	607.02	609.53	42.908415	-86.195653
70034	JHC MW-15002	518378.917	12633974.821	625.97	628.87	42.907878	-86.193573
70033	JHC MW-15003	518069.863	12633990.368	628.31	630.63	42.907031	-86.193490
70032	JHC MW-15004	517864.558	12633547.120	624.92	628.44	42.906441	-86.195127
70031	JHC MW-15005	517781.423	12633905.007	624.37	627.30	42.906234	-86.193785
70028	JHC MW-15006	517535.735	12635481.661	624.74	627.58	42.905654	-86.187881
70027	JHC MW-15007	517540.502	12635742.724	624.82	627.70	42.905683	-86.186908
70025	JHC MW-15008	517560.390	12636031.246	632.43	635.30	42.905754	-86.185833
70024	JHC MW-15009	517779.126	12636014.800	632.33	635.32	42.906353	-86.185912
70023	JHC MW-15010	518009.361	12636011.459	632.55	635.57	42.906985	-86.185943
70029	JHC MW-15011	517540.496	12634931.588	627.71	630.83	42.905635	-86.189935
70045	JHC MW-15012	519214.841	12633675.278	632.59	635.66	42.910153	-86.194759
70046	JHC MW-15013	519207.188	12634025.153	632.40	635.25	42.910153	-86.193452
70044	JHC MW-15014	519419.850	12634254.118	635.13	638.18	42.910750	-86.192615
70043	JHC MW-15015	519715.111	12634186.634	632.46	635.20	42.911556	-86.192891
70042	JHC MW-15016	519956.792	12634198.522	631.81	634.64	42.912220	-86.192866
70037	JHC MW-15017	521074.309	12635685.320	613.69	616.61	42.915374	-86.187407
70038	JHC MW-15018	521075.536	12635979.612	614.26	617.02	42.915394	-86.186309
70039	JHC MW-15019	521058.673	12636351.996	609.81	612.86	42.915370	-86.184918
70040	JHC MW-15020	521059.974	12636589.953	609.04	611.90	42.915388	-86.184030
70041	JHC MW-15021	521065.933	12636839.055	610.70	613.65	42.915419	-86.183100
70014	JHC MW-15022	520479.719	12638430.236	620.92	623.79	42.913905	-86.177114
70010	JHC MW-15023	521927.205	12638205.162	617.01	619.98	42.917863	-86.178071
70056	JHC MW-15024	522366.013	12637322.677	613.79	616.62	42.919014	-86.181400
70007	JHC MW-15025	522702.978	12636668.146	614.14	617.17	42.919900	-86.183870
70006	JHC MW-15026	522495.091	12635971.882	615.09	618.04	42.919288	-86.186452
70057	JHC MW-15027	522394.860	12635097.509	614.77	617.30	42.918961	-86.189708
70002	JHC MW-15028	521646.198	12634105.336	611.03	613.80	42.916849	-86.193350
70000	JHC MW-15029	520503.524	12633774.295	608.08	610.95	42.913694	-86.194493
70036	JHC MW-15030	519760.827	12633044.373	604.05	607.17	42.911613	-86.197157
70020	JHC MW-15031	520118.003	12637801.509	632.94	635.87	42.912876	-86.179432
70013	JHC MW-15032	520779.281	12638667.931	611.32	614.29	42.914741	-86.176251
70012	JHC MW-15033	521075.809	12638598.117	618.08	620.99	42.915550	-86.176536
70011	JHC MW-15034	521335.834	12638568.896	612.90	615.97	42.916262	-86.176666
70022	JHC MW-15035	520112.933	12637510.259	632.53	634.28	42.912844	-86.180518
70019	JHC MW-15036	520099.800	12638094.344	617.94	618.34	42.912843	-86.178337
70017	JHC MW-15037	520083.044	12638436.693	614.28	616.06	42.912817	-86.177058

STATION	DESCRIPTION	WITNESSES	NORTHING (PLANT DATUM)	EASTING (PLANT DATUM)	NORTHING (UNIT 1 & 2)	EASTING (UNIT 1 & 2)	ELEVATION (PLANT DATUM)	ELEVATION (NAVD88 DATUM)
NED 1	SET 3-1/4" DOMED ALUMINUM CAP ON 3/4" ALUMINUM TOP SECURITY ROD MONUMENT		16259.8663	12360.7163			607.357	606.862
	DEPTH = 43' TO REFUSAL							
	SET MAG IN EAST SIDE OF POWER POLE	N26°W 90.83'						
	SET MAG IN NORTH SIDE OF POWER POLE	S63°W 185.96'						
	SOUTHWEST FACE OF S.B.C. RISER	N54°E 39.19'						
NED 2	SET 3-1/4" DOMED ALUMINUM CAP ON 3/4" ALUMINUM TOP SECURITY ROD MONUMENT		16584.3789	12791.7633			608.150	607.655
	DEPTH = 43' TO REFUSAL							
	SET "X" ON SOUTH LEG OF TRANSMISSION LINE TOWER	N25°E 82.25'						
	WEST FACE OF FENCE POST AT SOUTWEST CORNER OF FENCE AROUND SUBSTATION	N90°E 89.54'						
	SET MAG NAIL IN NORTH SIDE OF 10" PINE	S52°E 59.82'						
NED 3	SET 3-1/4" DOMED ALUMINUM CAP ON 3/4" ALUMINUM TOP SECURITY ROD MONUMENT		16566.3834	13451.8335			609.457	608.962
	DEPTH = 47' TO REFUSAL							
	SOUTHEAST CORNER OF METAL GARAGE BUILDING	S28°W 93.60'						
	NORTHEAST CORNER OF METAL GARAGE BUILDING	S41°W 69.22'						
	MAG NAIL IN SOUTHEAST SIDE OF POWER POLE	N33°E 33.86'						
	FACE OF FENCE POST AT SOUTHEAST CORNER OF FENCE AROUND SUBSTATION	N49°W 11.34'						

PV 10.27.15 MN 11.25.15 REVISIONS PER CONSUMERS ENERGY REVIEW A 11.25.15 REFERENCE DRAWINGS REV DATE DESCRIPTION BY APP REV DATE DESCRIPTION DESCRIPTION DRAWING NO.



Grand Rapids 217 Grandville Ave., Suite 302 Grand Rapids, MI 49503 Ann Arbor, Chicago, Columbus, Holland, Indianapolis, St. Louis CAMPBELL PLANT MONITORING WELLS CCR MONITORING

UNITS 1 □ 2 22345base.DWG 1" = 300' SG-22345 583-009-441

APPENDIX A Low Stress (Low Flow) Purging and Sampling of Groundwater **Monitoring Wells SOP (Procedure CHEM-2.7.06)**

CONSUMERS ENERGY

Chemistry Department

PROC CHEM-2.7.06 PAGE 1 OF 14 REVISION 1

Standard Analytical Procedure

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

Written or Revised by	Katharyn L Schlueter Level I or Above	_ Date _	08/07/09	
Technical Review by	Gordon L Cattell Level II or Above (not author)	_ Date _	08/07/09	
Technical Approval by	Emil Blaj Level III	_ Date _	08/07/09	

This electronically produced document has been reviewed and approved by the above-named individuals. The original document bearing the approval signatures is maintained on file by Consumers Energy, Laboratory Services.

Standard Analytical Procedure

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

1.0 SCOPE

- 1.1 This procedure is a general method for collecting low stress/low flow ground water samples from monitoring wells. Upon approval by the responsible party, this procedure may be used as a substitute for macro-purging techniques where 3 to 5 well volumes have traditionally been purged prior to sampling. The low stress/low flow method is the preferred technique for ground water monitoring wells located at the former Manufactured Gas Plant (MGP) sites of Consumers Energy.
- 1.2 The presented technique applies to monitoring wells that have an inner casing with a nominal diameter of at least 1.0 inch, and maximum-screened lengths of ten feet per interval.
- 1.3 The technique is appropriate for collection of ground water samples that will be analyzed for: volatile and semi-volatile organics including pesticides and polychlorinated biphenyls (PCBs), total and dissolved metals, and various other analytes such as sulfates, cyanides, and nitrates/nitrites.
- 1.4 The technique is also appropriate when the following conditions are desired: lower turbidity in the sample containers, significantly less purge water for disposal, and higher analyte repeatability.

2.0 APPLICABLE DOCUMENTS AND REFERENCES

- 2.1 CHEM-1.1.02, Chemistry Department Procedure Requirements.
- 2.2 Ground Water Issue, Low-Flow (Minimal Drawdown) Ground-Water Sampling Procedures, Puls and Barcelona, USEPA, Office of Research and Development, Office of Solid Waste and Emergency Response, EPA/540/S-95/504, April 1996.
- 2.3 Low Stress (Low Flow) Purging and Sampling Procedure for the Collection of Ground Water Samples From Monitoring Wells, USEPA Region 1, SOP No GW 0001, Revision 2, July 30, 1996.
- 2.4 Technical Guidance on Low-Flow Purging and Sampling and Passive Sampling, D M and G L Nielson, The Nielson Environmental Field School, NEFS-TG001-99, December 1999.
- 2.5 Manufacturer Operation Manual, as appropriate.

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

- 2.6 Standard Guide for Purging Methods for Wells Used for Ground-Water Quality Investigations, D6452-99, American Society for Testing and Materials.
- 2.7 MDEQ RRD Operational Memorandum 2, Attachment 5, Sampling and Analysis, October 2004, Revision.
- 2.8 Field worksheets (Attachments A-D).

3.0 **DEFINITIONS**

- 3.1 COC Chain of Custody
- 3.2 NAPL Non-aqueous Phase Liquids
- 3.3 LNAPL Light Non-aqueous Phase Liquids
- 3.4 DNAPL Dense Non-aqueous Phase Liquids
- 3.5 DTW Depth-to-Groundwater

4.0 SUMMARY OF METHOD

4.1 Once depth-to-water is measured; a suitable pumping device is lowered to the target depth, generally mid-screen. Ground water is purged from the well casing at a slow rate, typically 100-500 mL/minute. While drawdown is measured and minimized, the purged water is diverted to a flow cell that contains several probes for indicating stabilization parameters, such as pH, conductively, etc. Once the parameters have stabilized within pre-determined limits, the purged water stream is diverted from the flow cell to sample containers for collection of proper test parameters.

5.0 PREREQUISITES

- 5.1 MEASURING AND TEST EQUIPMENT
- 5.1.1 Flow-cell, hand-held monitor, and sonde, containing in-line probes calibrated for at least dissolved oxygen and oxidation-reduction potential (ORP). If necessary, pH and conductivity may be monitored with external monitors, although in-line probes are recommended. Turbidity or other probes/monitors may be added as site-specific requirements dictate.

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

- 5.1.2 Adjustable rate groundwater pumping devices including: Peristaltic pump with pump head and electrical power source; bladder pump(s) with controller and a source of compressed air; gear pump (Keck or "bullet"), with controller and electrical power source. Gear and bladder pumps should be constructed of stainless steel or PTFE.
- 5.1.3 Tubing of the appropriate size, length, and material.
- 5.1.4 Interface probe for determining the presence or absence of NAPLs.
- 5.1.5 Water level measuring device with a minimum 0.01-foot accuracy.
- 5.1.6 Flow measurement supplies such as a rotometer or graduated cylinder with a stopwatch.
- 5.1.7 Portable PID meter, calibrated the same day as use.
- 5.1.8 Decontamination supplies, including deionized water, brushes, buckets, and commercially available 2-propanol soaked wipes.
- 5.1.9 Sample bottles with appropriate preservatives.
- 5.1.10 Field hazardous materials kit, including eyewash, sampling gloves, goggles, earplugs, etc.
- 5.1.11 Purge water collection device, such as a sturdy plastic bucket.
- 5.2 REAGENTS
- 5.2.1 Assorted standards as needed to fully calibrate the above system.
- 5.3 CALIBRATION REQUIREMENTS
- 5.3.1 All meters, probes, etc must be calibrated according to manufacturer's instructions. Periodic checks are recommended during or at the end of the day to ensure the calibration curves. Written documentation is required for all calibrations and periodic checks.
- 5.3.1.1 In general, daily recalibration will be required. In some cases where a periodic check indicates the calibration curves are still valid, no daily calibration may be necessary.

5.4 QUALITY CONTROL DOCUMENTS AND RECORDS

- 5.4.1 Historical documentation, including well construction data (eg, screen depth), well location map, and field data from a previous sampling event.
- 5.4.2 Material Safety Data Sheets (MSDSs) for all reagents taken to the job site.
- 5.4.3 A field log book or field worksheet must be kept at each sampling event (see Attachments A-D). The following should be documented:
- 5.4.3.1 Field instrumentation calibration data.
- 5.4.3.2 Monitoring well identification number and physical condition.
- 5.4.3.3 Monitoring well data such as casing material, casing diameter, and screen length.
- 5.4.3.4 Monitoring well depth and DTW, measurement technique, date and time of measurement.
- 5.4.3.5 Presence and thickness of NAPLs and detection method.
- 5.4.3.6 Sample tubing material, diameter, length, placement, and pump type.
- 5.4.3.7 Pumping rate, water level, water quality indicator values, date and time of measurements.
- 5.4.3.8 Identification of any unacceptable water quality indicator values.
- 5.4.3.9 Time and date of sample collection.
- 5.4.3.10 Sample ID and control number.
- 5.4.3.11 Field observations.
- 5.4.3.12 Sampler's name or initials.
- 5.4.4 The COC must contain the analytical parameters requested, sample time and date, sampler's name or initials, site location, sample ID, control number, preservatives added, and filtration status.

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

- 5.4.5 The sample labels must contain the sample ID, control number, sample time and date, sampler's initials, preservative, filtration status, and analytical parameter requested.
- 5.4.6 Field worksheets (Attachments A-D).
- 5.4.6.1 Monitoring Well Sampling Worksheet (Attachment A)
- 5.4.6.2 Monitoring Well Depth-To-Water Measurements Worksheet (Attachment B)
- 5.4.6.3 Flowcell/Sonde Calibration and Periodic Checks Worksheets (Attachment C)
- 5.4.6.4 Field Screening of Monitoring Wells Via PID (Attachment D)
- 5.5 PERSONNEL REQUIREMENTS
- 5.5.1 All tests and data reporting shall be performed by certified persons of Level I or above, in the appropriate discipline. (The project report shall be issued and reviewed by a certified person of Level II or above, in the appropriate discipline. The project report, if so indicated on the work request [or form similar in intent], may require approval from a certified person of Level III, in the appropriate discipline.)
- 5.6 ENVIRONMENTAL CONDITIONS

See Section 6.0.

6.0 PRECAUTIONS

- 6.1 The site-specific Health and Safety Plan is used to identify any physical or chemical precautions and actions to be taken to prevent injury. A pre-job briefing shall be conducted prior to initiating sampling.
- 6.2 Observe normal safety practices as specified in the latest online revision of the Environmental and Laboratory Services Accident Prevention Manual and the Consumers Energy Chemical Hygiene Plan in Lotus Notes.

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

7.0 LIMITATIONS AND ACTIONS

- 7.1 This technique is generally not suitable for very low-yield wells (<50 mL/minute with continued drawdown).
- 7.2 Even with pre-planning, a number of problems may be encountered which will challenge the sampler. These include: insufficient yield, failure of one or more key indicator parameters to stabilize, cascading, and equipment failure. Each of these problems will be addressed on a case-by-case basis and their impact can be minimized by consulting the references in Section 2.
- 7.3 This method does not address the collection of light or dense non-aqueous phase liquids (LNAPLs and DNAPLs). Collection of these sample types is both atypical and non-standardized and must therefore be addressed on an as-needed basis.

8.0 ACCEPTANCE CRITERIA

Refer to Section 9.3.9.3 in this procedure.

9.0 PROCEDURE

- 9.1 Orient the equipment and yourself upwind of the monitoring wells if possible.
- 9.2 DETERMINATION OF DEPTH-TO-GROUNDWATER (DTW)
- 9.2.1 Start at either the well known, or believed to have, the least contaminated groundwater and proceed systematically to the well known, or believed to have, the highest level of contamination.
- 9.2.2 Check the well casing protector, lock, locking cap, and well casing for obvious damage or evidence of tampering. Record any abnormal observations.
- 9.2.3 The sampler may desire to minimize contamination from the ground and provide a clean area for laying down equipment. This can be accomplished by cutting a section from a sheet of plastic and fitting it around the well casing protector.
- 9.2.4 Remove the well cap. At some sites, it may be necessary to remove all well caps first, then proceed to 9.2.5. This will be determined prior to any field events.

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

- 9.2.5 If the site has not been characterized yet, or there is insufficient history, it will be useful to determine the concentration of organic vapors in the heads case. Using a portable, calibrated, PID meter measure and record the organic vapor concentration as follows: (1) At the highest risk breathing zone elevation, defined here as the point located at roughly 6" above the center of the top of the well casing. (2) At 0-6" within the well casing.
- 9.2.6 If the well casing does not have a reference point, make one. The reference point is typically a V-cut or an indelible mark in the well casing.
- 9.2.7 Measure and record the DTW to 0.01 feet. Duplicate the reading. Hold the tape against the reference point when making the reading. Care should be taken to minimize disturbance of the water column.
- 9.2.8 Measure and record the thickness and depth of any NAPLs.
- 9.2.9 If desired or required by the site plan, measure the depth of the well. Care should be taken to minimize disturbance of the water column and any sediment that has accumulated.
- 9.2.10 Decontaminate the electronic tape and interface meter. Wipe dry using a clean Kaydry-type material. Rinse with DI water and wipe dry again. If organic contamination is suspected, the sampler must decontaminate accordingly before proceeding. One option is to use commercially prepared decontamination wipes that are saturated with 2-propanol.
- 9.2.11 If the monitoring well will be sampled the same day and will remain in visual range and/or without a reasonable risk of tampering, loosely recap the well and leave the well casing protector unlocked. Otherwise, secure the well as if not returning.
- 9.2.12 If a sheet of plastic has been fitted around the well casing protector, leave it in place if the well will be sampled the same day.
- 9.2.13 Continue with the determination of DTW on the rest of the monitoring wells. Continue with purging and sampling when appropriate (ie, large distance between wells).

PROC CHEM-2.7.06 PAGE 9 OF 14 REVISION 1

Standard Analytical Procedure

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

9.3 PURGING

- 9.3.1 If not already determined at the laboratory or by prior sampling events, determine the type of pump to be used (operation of each pump type will not be covered here).
- 9.3.2 For ease of use and portability, a peristaltic pump may generally be used for any well where DTW plus casing height above grade does not exceed 15 feet.
- 9.3.3 Keck (gear or "bullet") and bladder pumps can be used in any instance where there is sufficient water in the casing to completely submerge the pump and intake screen at all times.
- 9.3.4 Use well installation and historical data to determine the length of tubing needed to place the pump intake or tubing at the desired sample depth, generally mid-screen. Attach the tubing to the pump and prepare to lower the tubing or tubing/pump down the well. To keep from introducing contamination into the monitoring well, never allow the tubing or tubing/pump to touch bare ground.
- 9.3.5 Install the tubing or pump/tubing. Slowly lower the pump, tubing, and any safety cable and electrical lines into the monitoring well. Final placement is generally at mid-screen. Typically, the intake must be kept at least 2 feet above the bottom of the well to prevent disturbance and resuspension of any sediment or NAPL present in the bottom of the well. Once the desired depth is reached, clamp or otherwise secure the tubing to prevent the pump/tubing from dropping any lower. Record the depth to which the pump was lowered.
- 9.3.6 Before starting the pump, wait a few minutes and measure the water level again. Record this level. This short waiting period allows for reduced turbidity and reequilibrium of the water level. Leave the electronic tape in the well for later use.
- 9.3.7 Attach the in-line flow cell. Start the pump and collect roughly 100 mL/minute. Start with a faster or slower pumping rate if historical data suggests to do so.
- 9.3.8 Collect all water for proper disposal.
- 9.3.9 Monitor and record the water quality parameters and water level every 3-5 minutes.

- 9.3.9.1 Ideally, a steady flow rate should be maintained that results in a stabilized water level. Pumping rates should be reduced or increased to ensure stabilization of the water level in the well. Avoid entrainment of air in the tubing.
- 9.3.9.2 Record the time of the readings and the pump rate.
- 9.3.9.3 The well is considered stabilized and ready for sample collection when the indicator parameters have stabilized for three consecutive readings as follows:
 - ± 0.1 pH units
 - ± 3% conductivity units (specific conductance)
 - $\pm 10 \text{ mV}$ for redox potential (Eh/ORP)
 - $\pm 10\%$ for DO and turbidity
 - Temperature For information only. Record only.

Dissolved oxygen and turbidity usually require the longest time to achieve stabilization. (Above criteria may not apply to very clean wells.)

9.4 SAMPLE COLLECTION

- 9.4.1 The pump must not be removed from the well between purging and sample collection. It is recommended that the pump not be turned off between purging and sample collection. Continue to collect excess groundwater for proper disposal.
- 9.4.2 Disconnect or bypass the flow cell.
- 9.4.3 Collect samples at the same flow rate as the purging rate. Minimize potential contamination from dust, rain, etc by shielding the open bottles as needed.
- 9.4.4 Samples will be collected directly into the sample containers. Minimize aeration by allowing the water to flow down the side of the container rather than splashing against the bottom of the bottle. Avoid placing the sample tubing below the liquid level of the sample being collected. Label the containers and chill immediately.
- 9.4.5 VOC samples must be collected first except as noted below for Low Level Mercury. Check for air bubbles in the container before proceeding to collecting the next parameter. Carbonacious waters will naturally produce bubbles in the containers, which cannot, and should not, be removed.

NOTE: A sample for low level mercury should be the first sample collected when multiple analyte containers will be filled. Low level mercury sample bottles should be pre-cleaned and individually stored in Ziploc®-style plastic bags. Use clean nitrile gloves for each sample collection point, immediately prior to handling any bagged sample bottles.

When collecting a sample from a monitoring well:

- Remove the sample bottle from the plastic bag and remove the cap.
- The bottle should be thoroughly rinsed with the sample stream, holding the sample tubing very close to, not within, the open bottle (approximately 1/8"). Never place the sample tubing within the bottle.
- Fill to approximately ¼" below the bottle threads, affix a label, cap the bottle, and return it to the plastic bag.
- Place the bagged bottle in a cooler designated only for low level mercury.
- 9.4.6 Semi-volatile samples must be collected next, followed by any other parameters that do not require filtration.
- 9.4.7 Samples that require only filtration with no additional preparation steps should be collected using in-line filters. Filtered samples are typically collected last One exception is collection for available cyanide, which must be collected last due to the potential for cross-contamination from the lead carbonate reagent.
- 9.4.8 Once all samples from the monitoring well are collected, remove the tubing or pump/tubing. Record the stop time, if required. In addition, the total volume purged can be calculated and recorded.
- 9.4.9 Cap and secure the monitoring well.
- 9.4.10 In general, the purged water is poured on to the ground next to the monitoring well. Whether to collect in a drum or to use another strategy will be determined prior to starting any field activities.
- 9.4.11 Continue with sampling all of the other monitoring wells.

9.5 FIELD QUALITY CONTROL (QC) SAMPLES

9.5.1 Field QC samples must be collected to determine if sample collection and handling procedures have adversely affected the quality of the ground water samples. All QC samples are treated the same as samples with regard to volume, bottle type, preservatives, and any pretreatment.

9.5.2 TYPES OF QC SAMPLES

- 9.5.2.1 Trip Blank For VOCs only. Consists of DI water in a VOC vial (contains preservative) and is prepared at the lab prior to the field event. The vial is left capped and chilled while sampling. Used to determine if sample holding and transport has introduced contamination into the samples.
- 9.5.2.2 Field Blank Consists of DI water in an appropriate bottle with the appropriate preservative. Obtained from the lab prior to the sampling event and can prepare for a variety of analytes. The bottle is uncapped while sampling to indicate contamination that may have occurred during the operation.
- 9.5.2.3 Equipment Blank DI water is exposed to the sample path at any time decontamination needs to be verified. Collect for any suspect parameter and treat it exactly the same as if collecting a sample.
- 9.5.2.4 Sample Duplicate One monitoring well per 20 will be selected for collection of a duplicate sample. This is simply an additional set of the sample collected in exactly the same manner as the original sample. The sample type is used to determine precision.
- 9.5.2.5 Matrix Spike and Matrix Spike Duplicate One monitoring well per 20 will be selected. These are additional sets of samples collected in exactly the same manner as the sample is collected. This sample type is used to determine accuracy but can also indicate matrix bias.

9.6 DECONTAMINATION

9.6.1 **General Considerations**

- 9.6.1.1 All nondedicated sampling equipment that is to be reused must be decontaminated prior to its reuse.
- 9.6.1.2 All disposable tubing will be properly discarded and new tubing used in its place. No tubing will be reused.
- 9.6.1.3 All equipment washings/rinsates must be collected for proper disposal.

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

- 9.6.1.4 The flow cell may be cleaned using the procedure in Section 9.6.2.1 or a manufacturer recommended procedure. Special attention must be paid to care of the probes on the sonde portion of the unit.
- 9.6.1.5 To avoid cross-contamination, pumps that are contaminated with NAPLs will be isolated and decontaminated at the laboratory.

9.6.2 Between Well and End-of-Day Decontamination Process

9.6.2.1 Flow Cell

- A. In the case of the flow cell when new tubing will be used, a double rinse at half volume using deionized water is typically adequate. Continue with sampling. If the sample location is historically not contaminated, this step may be omitted.
- B. If NAPLs, odors, or colors are present and cannot be flushed out, assess if the probes are fouled by spot-checking the calibration curves. If the probes are not fouled, no further action is necessary since the flow cell does not contact the sample. Continue with sampling.
- C. If the probes are fouled, contact the MGP sample coordinator at the laboratory for guidance.
- D. At the end of the day, the in-line flow cell should be free of sediment and NAPLs. Fill the cell with tap water, insert the sonde, and store.

9.6.3 **Pumps**

- 9.6.3.1 Peristaltic pumps need to only have the pump head tubing and sample tubing replaced.
- 9.6.3.2 If the equipment, such as the peristaltic pump case, is contaminated with organic material, wipe down with commercially available wipes presaturated with 2-propanol. If the organic material does not dislodge, stop now, isolate for decontamination at the lab, and use different equipment for the next monitoring well.

9.6.4 Specific Bladder and Keck (gear or bullet) Pump Decontamination Measures

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

- 9.6.4.1 Pump pre-rinse Operate the pump in a deep basin containing 1-5 gallons of deionized water and continue through several cycles.
- 9.6.4.2 Pump wash Operate the pump in a deep basin containing 1-5 gallons of nonphosphate detergent solution, such as Alconox. Operate through several cycles.
- 9.6.4.3 Pump rinse Operate the pump in a deep basin containing 1-5 gallons of DI water. Continue for several cycles.
- 9.6.4.4 Disassemble pump, if required, and continue with 9.6.4.5. If not required, go to 9.6.4.7.
- 9.6.4.5 Pre-rinse, wash, and rinse as above, scrubbing as needed at the wash stage.
- 9.6.4.6 Reassemble the pump.
- 9.6.4.7 Store the pump so as to keep it clean until needed.

10.0 CALCULATIONS

None

11.0 DATA REPORTING

Refer to Section 5.4 in this procedure. At a minimum the COC shall be stored in the project folder.

Chemistry Department

Standard Analytical Procedure

PROC CHEM-2.7.06 PAGE 1 OF 1 REVISION 1 ATTACHMENT A

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

Consumers Energy Company Chemistry Section – Laboratory Services Department Monitoring Well Sampling Worksheet

MW_ID		Today's Date		Control Number		
Location				<u></u>		
MW Reference Name			GPS Grid Re	ference		
Top-of-Casing Elevation	(ft) Dep	oth-to-Screen Bot	tom (ft)	Depth-to-MidSo	creen (ft)	
Screen Length (ft)	Casing ID (in)	Typical Pu	ırge Volume	Protective Casi	ing Mount	
Comments						

Field Measurements

Depth-to-W	ater (ft)		HC La	yer Detected		PI	D Reading (p)	pm)	
Time	рН	Temp	Sp Cond	DO	DO	ORP	Pump Rate Indicate	Water Level	Turbidity
Hr : Min	Units	°C	μS/cm	ppm	% Sat	mV	mL/min gal/min	Draftdown (ft)	NTU
3-5 Min	± 0.1	na	± 3%	± 10%	± 10%	± 10%	See Notes	<0.33	± 10%
Completed 2				Total Pump			Total Purge		

Chemistry Department

Standard Analytical Procedure

PROC CHEM-2.7.06 PAGE 1 OF 1 REVISION 1 ATTACHMENT B

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

Monitoring Well Depth-to-Water Measurements

Site:		-
Analyst:		-
Date:	,	Sample
Project No:		-
Method:	Electronic Tape	-
Tape ID:	Solinst, Model 122, S/N 122001406-1	

Well ID Number	Time of Measurement	Trial 1 DWL, ft	Trial 2 DWL, ft	Depth to Bottom of Screen, ft	Remarks

Chemistry Department

Standard Analytical Procedure

PROC CHEM-2.7.06 PAGE 1 OF 2 REVISION 1 ATTACHMENT C

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

	Site or Project Tracking		
	Site or Project :	Chem. Control # :	
	System Identifiers	_	
	Monitor Brand, Model & S/N:	YSI 650MDS S/N 08C100135	
	Sonde Brand, Model & S/N:	YSI 6820V2 S/N 08C101426	_
	Flow Cell Brand & Model:	YSI 6160	Campl
	DO Probe Brand, Model & S/N:	YSI 6150 S/N 08C101539	- Sampl
	Turbidity Probe Brand, Model & S/N:	YSI 6136 S/N 08C101363	- -
	pH With ORP Brand, Probe Model & Lot:	YSI 6565 Lot Number 08B*26	_
	Conductivity & Temperature Probe Model & S/N:	YSI No additional information	_
I.	pH Check		
	Standard vs As-found, pH Units Standard Source	Catalog # & Lot #	Exp. Date
	4.00		
ſ	7.00		
	7.00		
	10.00	1989 and an artist and a second a second and	****
	Analyst Initials: As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re	points? Yes No ecalibration is required .	
	Analyst Initials: As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration	points? Yes No ecalibration is required .	performed. Yes No
	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project	points? Yes No ecalibration is required . t, indicate whether recalibration has been	performed. Yes No
	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration ORP Check With Zobell Solution Standard vs As-found, mV Source	points? Yes No ecalibration is required . t, indicate whether recalibration has been	performed. Yes No
	Analyst Initials: As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then relif 'No' and you are within, or at the end of project Note: If recalibration	points? Yes No ecalibration is required . t, indicate whether recalibration has been on was performed, the solutions listed abo	performed. Yes No ove were used.
	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration ORP Check With Zobell Solution Standard vs As-found, mV Source	points? Yes No ecalibration is required . t, indicate whether recalibration has been on was performed, the solutions listed abo Catalog # & Lot #	performed. Yes No ove were used.
v .	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration Standard vs As-found, mV Source 231 Analyst Initials: As-Found Evaluation Is the reading in the 221-241mV range? Yes No If 'No' and you are within, or at the end of project Note: If recalibration	points? Yes No ecalibration is required. t, indicate whether recalibration has been on was performed, the solutions listed abo Catalog # & Lot # Date & Time:	performed. Yes No ove were used. Exp. Date performed. Yes No
/ .	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration Standard vs As-found, mV Source 231 Analyst Initials: As-Found Evaluation Is the reading in the 221-241mV range? Yes No If 'No' and you are within, or at the end of project If 'No' and you are within, or at the end of project	points? Yes No ecalibration is required. t, indicate whether recalibration has been on was performed, the solutions listed abo Catalog # & Lot # Date & Time: ecalibration is required. t, indicate whether recalibration has been	performed. Yes No ove were used. Exp. Date performed. Yes No
/. 	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration Standard vs As-found, mV Source 231 Analyst Initials: As-Found Evaluation Is the reading in the 221-241mV range? Yes No If 'No' and you are within, or at the end of project Note: If recalibration	points? Yes No ecalibration is required. t, indicate whether recalibration has been on was performed, the solutions listed abo Catalog # & Lot # Date & Time: ecalibration is required. t, indicate whether recalibration has been on was performed, the solution listed above	performed. Yes No ove were used. Exp. Date performed. Yes No ve was used.
/. 	As-Found Evaluation Are the readings within +/- 0.10 of their calibration If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration Standard vs As-found, mV Source 231 Analyst Initials: As-Found Evaluation Is the reading in the 221-241mV range? Yes No If 'No' and you are at the start of a project, then re If 'No' and you are within, or at the end of project Note: If recalibration DO Check With DI Water; 100% Saturation	points? Yes No ecalibration is required. t, indicate whether recalibration has been on was performed, the solutions listed abo Catalog # & Lot # Date & Time: ecalibration is required. t, indicate whether recalibration has been on was performed, the solution listed above	performed. Yes No ove were used. Exp. Date performed. Yes No ve was used.

Chemistry Department

Standard Analytical Procedure

PROC CHEM-2.7.06 PAGE 2 OF 2 REVISION 1 ATTACHMENT C

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

oject Sonde Check; As-F	ound Reading	s & Recalibration	Page 2 of 2
Site or Project:		Chem. Control #	
Conductivity Check			
Standard vs As-Found, us	Source	Catalog # & Lot #	Exp. Date
0 (DI Water)	Lab DI System		
Analyst Initials:		Date & Time	:
•	a project, then reca the end of project, i		
Linearity Check			
Standard vs As-Found, us	Source	Catalog # & Lot #	Exp. Date
Standard vs As-Found, NTU 0 (DI Water)	Source Lab DI System	Catalog # & Lot #	Exp. Date
	-		
Analyst Initials: _		Date & Time	:
<u>-</u>	a project, then reca the end of project,		
Linearity Check			
Standard vs As-Found, NTU	Source	Catalog # & Lot #	Exp. Date
Analyst Initials: _	****	_ Date & Time	e:

Chemistry Department

Standard Analytical Procedure

PROC CHEM-2.7.06 PAGE 1 OF 1 REVISION 1 ATTACHMENT D

TITLE: LOW STRESS (LOW FLOW) PURGING AND SAMPLING OF GROUND WATER MONITORING WELLS

Field Screening of Monitoring Wells Via PID

Project Informa	tion		
Site:			6 1
Project No:			Sample
Date:			
Instrument Info	rmation		
Instrument ID an	d Serial Number:		
Calibration (Spar	n) Gas ID, Lot Number	Concentration, etc:	
Zero Gas ID, Lot	Number, Concentration	on, etc:	
Periodic Calibra	ntion Checks		
Time	Analyst	Cal Gas Conc, ppm v/v	Display Conc, ppm v/v

Monitoring Well Screening

MW ID	Time	Analyst	Breathing Zone Display Conc	0-6" Within Casing Display Conc
Background Air				NA

APPENDIX B Chain-of-Custody, Handling, Packing and Shipping SOP (Procedure CHEM-1.2.04)

General Standard Operating Procedure

TITLE: CHAIN OF CUSTODY REQUIREMENTS (CoC)

1.0 PURPOSE

To provide guidance for uniform preparation of a Chain-of-Custody document.

2.0 SCOPE

The Chain-of-Custody (CoC) document is required for all samples where the analysis results are used for environmental reporting. It may also be used as requested by the customer for other forms of reporting. This method provides guidance for the use of the CoC document.

3.0 **DEFINITIONS**

Chain-of-Custody (CoC) – A document that is a management tool used to verify sample identification information, sample inventory and sample possession from the time the sample is collected to the time the sample is received by a laboratory.

4.0 REFERENCE DOCUMENTS

- 4.1 Chapter 1 SW-846, Test Method for Evaluating Solid Waste, USEPA
- 4.2 ASTM Method D 5283-92, Standard Practice for Generation of Environmental Data Related to Waste Management Activities: Quality Assurance and Quality Control Planning and Implementation
- 4.3 ASTM Method D 4840-95, Standard Guide for Sampling Chain-of-Custody Procedures
- 4.4 Chemistry Department Standard Operating Procedures, as applicable
- 4.5 Laboratory Services Quality Assurance (LSQA) Procedure Manual, as applicable

5.0 PROCEDURE

5.1 Prior to sampling, the sample team shall be provided with CoC forms. It shall be the responsibility of the on-site supervisor or designated representative to ensure that CoC requirements, sample collection protocol and proper sample handling protocol are initiated on-site.

TITLE: CHAIN OF CUSTODY REQUIREMENTS (CoC)

- 5.2 A sample is considered under custody if one or more of the following criteria are met:
 - The sample is in the sampler's possession.
 - The sample is within the sampler's view after being in possession.
 - The sample was in the sampler's possession and then placed in a secure container to prevent tampering.
 - It is in a designated secure area.
- 5.3 Each CoC shall identify basic site information and include the following:
 - The sampling site name, project name or other site/project identification.
 - The initials of the sampling teams.
 - Project Leader or report distribution personnel.
 - If a site sketch or other documents are to be found with the CoC.
 - Necessary remarks as required.
- 5.4 Each sample entry into the CoC shall include the following:
 - Date of sample collection.
 - Time of sample collection.
 - Type of sample matrix (soil, water, vapor, product, etc).
 - Sample identification, name or description.
 - Sample depth, if applicable.
 - Number of sample containers.
 - Specific analytical test parameters. In some cases the specific test parameters may not be known at the time of sample collection. However, the samples are collected in accordance with the protocol for a general group of analytes (e.g., dissolved metals, volatile organic compounds) and the specific test analytes are determined after the sampling event. In these cases, the entry for the analytical test parameter is not required.
- 5.5 The original of the CoC record shall accompany the samples and a copy should be maintained by the on-site supervisor.
- 5.6 When transferring the possession of samples, the individuals relinquishing and the individuals receiving the samples should sign, date and note the time on the CoC record.
- 5.7 In cases where the sample leaves the originator's immediate control, such as shipment to the laboratory by a common carrier (e.g., Federal Express or

Chemistry Department

General Standard Operating Procedure

PROC CHEM-1.2.04 PAGE 3 OF 3 REVISION 0

TITLE: CHAIN OF CUSTODY REQUIREMENTS (CoC)

Consumers Energy's internal mail) a seal should be placed on the shipping container to detect unauthorized entry to the samples. Any shipping containers that arrive at the Laboratory with the seals damaged should be evaluated to ascertain if the contents have been in valid custody.

- 5.8 In the event samples requiring the CoC protocol arrive at the Laboratory without the CoC document, the Laboratory shall complete the CoC document upon sample login and under the supervision of the assigned Laboratory Project Leader or Area Coordinator. The person completing the CoC shall enter the statement "CoC completed by the Laboratory upon receipt of sample(s)" in the remarks section of the CoC and initial the entry.
- 5.9 A sample CoC form is attached (Attachment A).
- 5.10 Other CoC formats and forms may be used as long as the CoC meets the recommendations of this procedure.
- 5.11 The CoC shall be stored in the project folder and retained according to CHEM-1.1.7, Record Retention.

QA Review	Katharyn L Schlueter	Date _	02/27/08	
Chemistry	Quality Assurance Coordinator			
Administrative Approval	Gordon L Cattell	Date _	02/27/08	
11	Chemistry Department Supervisor			

This electronically produced document has been reviewed and approved by the above-named individuals. The original document bearing the approval signatures is maintained on file by Consumers Energy, Laboratory Services.

General Standard Operating Procedure

PROC CHEM-1.2.04 PAGE 1 OF 1 REVISION 0 ATTACHMENT A

TITLE: CHAIN OF CUSTODY FORM (CoC)

,			0	CHAIN OF CUSTODY	OF	2	IST	0	O	>		
Consumers Energy	Energy	VO O	VSUME	CONSUMERS ENERGY COMPANY – LABORATORY SERVICES	Y COMPAN	IY - L,	ABORA	70	Y SI	ERVI	CES	
		135 WE	STTRA	135 WEST TRAIL ST., JACKSON, MI 49201 • (517) 788-1251	i, Mi 49201	(517)	788-1251	•	AX (5	• FAX (517) 788-2533	8-25	33
SAMPLING SITE:				PROJECT NUMBER:				A	ALYSIS R	ANALYSIS REQUESTED	٥	PAGE OF
												SEND REPORT TO:
SAMPLING TEAM:				DATE SHIPPED:	IIIS	SITE SKETCH ATTACHED? CIRCLE ONE:	TACHED? VE:					
CE	SAMPLE	SAMPLE	SAMPLE			z	10 # 0F					PHONE
CONTROL#	DAIE	IME	MAIHIX	SAMPLE DESCRIPTION / LOCATION	ION / LOCATION	DEPTH	CONTAINERS	+	+	+	+	HEMAHKS
								+	_		-	
								+				
								-				
								-				
RELINQUISHED BY: (SIGNATURE)	Y: (SIGNATURE		DATE/TIME	ME	RECEIVED BY: (SIGNATURE)	(TURE)					COMMENTS	AENTS
RELINQUISHED BY: (SIGNATURE)	Y: (SIGNATURE	6	DATE/TIME	ME	RECEIVED BY: (SIGNATURE)	(TURE)						
RELINQUISHED BY: (SIGNATURE)	Y: (SIGNATURE		DATE/TIME	IME	RECEIVED BY: (SIGNATURE)	(TURE)						
			-						Š	ORIGINAL TO LAB	1	COPY TO CUSTOMER



Arcadis of Michigan, LLC

10559 Citation Drive
Suite 100
Brighton, Michigan 48116
Tel 810 229 8594
Fax 810 229 8837

www.arcadis.com